

TRANSPORTATION OF 4 units of Modules



KEY INFORMATION

| | |
|-------------------------|--|
| Name of project | Future Growth Project / Wellhead Pressure Management Project – Voyage 04 |
| POL/POD | Okpo, Republic of Korea / Hamina, Finland |
| TOS | Jun 28, 2018 ~ |
| Cargo | 4 units of modules |
| Vessel | MV “CY INTEROCEAN I” |
| Contractor | COSCO Shipping Specialized Carrier Co., Ltd. / Dongbang Transport Logistics Co., Ltd |
| Total steaming distance | approx. 12,400 nm |
| Scope of work | Sea-transport of cargoes by deck ship Project Management including Load-out / In operations Engineering <ul style="list-style-type: none"> - Stability & Long. strength Check - Ballast Calculation - Check of structural strength of vessel’s deck - Preparation of transportation manual Ballasting of vessel during loading & discharging |

CARGO DESCRIPTION

| Description | Q'ty | Dimensions(m) | | | Weight (ton) |
|--------------|--------|---------------|-------|--------|--------------|
| | | Length | Width | Height | |
| Air Coolers | 1 unit | 43.1 | 16.3 | 10.8 | 636.0 |
| Air Coolers | 1 unit | 40.6 | 16.3 | 10.5 | 605.0 |
| Coolers Supt | 1 unit | 41.8 | 16.2 | 10.8 | 259.9 |
| Cooler Supt | 1 unit | 41.7 | 16.2 | 11.3 | 368.3 |



CHUNG YANG Shipping CO., LTD.

#2302, Centum Leaders Mark Bldg.,
17 Apec-ro, Haeundae-gu, Busan, Korea.
Tel : +82 51 745 9100 Fax : +82 51 745 9101
e-mail : cyship@cyship.co.kr